

Grezzana, 10/01/2022

## **Product information and data on Installation, cleaning and aftercare**

Please also see attached data sheets for full details on all the above, these sheets are in addition to the main pages and are here to assist you with your initial choice of product and product finish.

### 1: AREA OF APPLICATION.

VENISTON , are always very keen to ensure that their clients and their clients projects have the desired finish when completed, so to this end we like to ensure that the correct product and product finish is installed at all times, it is advisable to inform us of the areas that you intend to use the product in i.e. heavy commercial, light commercial, restaurant, office development, residential and so on, so that VENISTON S.r.l. can assist you and advise you on the right choices from the start to the completion of the project.

Once we have this information then we would be in a position to advice as to whether it would be better to have a prefinished product or a product that would require on site grinding.

We are here to assist you at all time to ensure that you are getting the most suitable product for your project.

### 2] FACTORY FINISHES

At Veniston, we can supply the client with a factory treated product.

The tile will still have to be sealed on site after installation. The production line sealer is only a thin coating and is applied as a basic coat only and not a fully sealed product.

Both of these solutions will require on site care as in the paragraph below and in our standard instillation instructions.

*Page 1/2; dated 10/01/2022*

### 3] ON SITE SEALING AND FLOOR PROTECTION

VENISTON, feels and knows that this area is one of the most important areas of all to ensure that the client has the floor he desires. We cannot stress how important this area of the installation is.

A] All products must be full cleaned after the installation; this can be done either manually or mechanically depending on the total area to be cleaned. This is to ensure that residue/grout/dirt par from the installation are removed from the surface of the tile and the surrounding area.

B] After cleaning it is imperative that the floor/product is sealed correctly and we would advise you to contact your local supplier for information as to how to do this, there are a number of good suppliers in the market.

C] It is also advisable to test the sealer on a number of sample pieces prior to applying the sealer too the completed floor area that has been installed, we have found that the easiest solution is to contact the local technical representative of the Sealer producer.

Please ensure that all technical data from the Sealer producer is followed accurately at all times during all the procedures.

D] Floor protection is imperative once the above steps have been carried out to ensure that there is no damage occurs from other trade/tradesmen working on and around the vicinity of the newly finished floor area, the floor should be protected with a good quality covering to alleviate any damage or spillages from other trades.

### 4] STORAGE PROCEDURES

A] VENISTON engineered terrazzo products should be installed as soon as possible after arriving either on site or at the contractor/distributors premises.

B] All terrazzo tile products should be stored indoors and not left outside in direct sunlight.

C] Storing Terrazzo tiles for long periods of time out with the above mentioned points A] and B] may cause side effects of the product drying out.

D] All Terrazzo tile stored must be inspected on a regular basis whether they are being stored on site or at the contractor/distributors premises.